

# **Operating Manual**



# **HARVEY Pro**

Version 1.4 (April 2020)

DSPECIALISTS Digitale Audio- und Messsysteme GmbH Helmholtzstr. 2-9 L D-10587 Berlin

www.harvey.audio

© DSPECIALISTS GmbH, Berlin

# **Table of Contents**

Im	oorta	nt Safety Instructions	5		
FC	C Us	er Information	6		
1	Introduction				
	1.1	Features of the HARVEY Composer Software	8		
	1.2	Information about the HARVEY Devices	8		
2	Unp	acking	10		
3	Swit	ching on the Device	11		
4	Status and Settings on the Front Panel				
	4.1	Status Light	12		
	4.2	Main Menu	13		
5	Interfaces on the Rear Panel				
	5.1	Mains Power Supply Inlet	19		
	5.2	Network Control Interface	20		
	5.3	RS232 Control Interface	21		
	5.4	RS485 / DMX Control Interface	22		
	5.5	Digital Input Control Interface (GPI)	24		
	5.6	Analog Input Control Interface (AIN)	26		
	5.7	Digital Output Control Interface (GPO)	28		
	5.8	Relay Contact Interface (GPO)	30		
	5.9	Dante Network Audio Interface (Optional)	31		
	5.10	Analog Audio Line Output Interface	32		
	5.11	Analog Audio Mic / Line Input Interface	34		
6	HARVEY Pro Models				
	6.1	HARVEY Pro versus HARVEY mx.16	38		
7	HAR	<b>VEY Pro Specifications Summary</b>	39		



## **Important Safety Instructions**



This symbol indicates the need for the user to read and understand the following instructions for a safe operation of the equipment.

- 1. Read these instructions. Keep these instructions.
- 2. Never remove screws from the enclosure to reduce the risk of electric shock. There are no user-serviceable parts inside. Refer all servicing to qualified service personnel only.
- 3. The device is intended exclusively for operation in a standard 19" rack or switch cabinet. For this purpose, mount the device at the rackmounts with four screws to the 19" rack or cabinet.
- 4. Only connect the unit to a grounded 3-pole AC outlet with rated 100-240 V ~ 50-60 Hz.
- 5. Be sure to connect the unit to a mains installation only, which is equipped with an overcurrent protective device rated at 20 A maximum.
- 6. Before use, always make sure that the mains power cord is in good condition. Never remove the protective earthing conductor of the power cord. Dispose and replace a damaged power cord immediately.
- 7. A maximum of 20 AC mains supplied external devices is allowed to be connected to the interfaces of the device.
- 8. The power switch is located on the rear panel of the unit. The ON and OFF positions are marked as "1" and "0", respectively.
- 9. Install the unit in a cool, dry, and clean place with sufficient ventilation. Do not expose it to direct sunlight, heat sources, vibrations, dirt and dust, humidity, and too low temperatures.
- 10. Do not block the ventilation openings. Allow for a clearance of 2.5 cm (1") around the unit to prevent overheating.
- 11. When exposing the unit to considerable temperature changes, be sure to allow for it to adjust to the new conditions. Such variations in temperature may cause condensation inside the unit, resulting in failure and the risk of electric shock.
- 12. Overexposure to high sound levels can result in hearing damage or loss. Be sure to wear ear protectors when exposed to such sound levels.
- 13. Consult the HARVEY Pro operating manual to use the device under the intended operating conditions.

## FCC User Information

Note: This equipment has been tested and found to comply with the limits for a Class A digital device, pursuant to Part 15 of the FCC Rules. These limits are designed to provide reasonable protection against harmful interference when the equipment is operated in a commercial environment. This equipment generates, uses, and can radiate radio frequency energy and, if not installed and used in accordance with this operating manual, may cause harmful interference to radio communications. Operation of this equipment in a residential area is likely to cause harmful interference, in which case the user will be required to correct the interference at his own expense.

## 1 Introduction

HARVEY<sup>®</sup> is a family of freely programmable audio and media control devices that are ideal for conference rooms, theaters, museums, home theaters, educational institutions or multipurpose halls, without being limited to these applications.

With a wide range of audio and control interfaces, HARVEY devices can connect to a wide range of devices and act as an intelligent control center for audio, lighting and media technology.

The integrated powerful digital signal processors (DSP) with their extensive software capabilities allow even for complex systems with a high number of audio channels a tailormade and high-quality audio processing in real time with minimal signal delay of less than a millisecond.

To control HARVEY and the devices connected to it all common media controls of wellknown manufacturers are suitable, such as Crestron, AMX, Cue and Apple, by using the integrated text protocol H-Text.

HARVEY devices also have the special ability to process and generate foreign protocols that can be programmed by you with almost no effort. In addition, they even allow data to be transferred between their serial interfaces (Ethernet, RS485, RS232), thus rendering additional converters superfluous.

Thanks to the integrated web server, graphical user terminals can be implemented quickly and easily for the end user.

All settings can be aggregated into scenarios, saved as a preset and recalled at the push of a button to quickly switch between different usage options of the installation.

The wall-mounted HARVEY RC4 and HARVEY RC12 network-based remote controls allow control of presets, audio levels and DMX lamps.

Both the HARVEY devices and the software have a modular structure. The programming of all HARVEY components is done conveniently via Windows computer with the freely accessible software HARVEY Composer.

By programming with the HARVEY Composer software offline - even without connected devices - new installations and changes can be planned and prepared from any location. The programmed project is transferred to the hardware via an IP network and fine-tuned on the device online and in real time in the HARVEY Composer software.

Although the HARVEY devices and the software are designed to be intuitive to use, we recommend that you read this HARVEY Device Operating Manual and the HARVEY Composer Manual carefully to exploit all possibilities of the HARVEY family.

### **1.1 Features of the HARVEY Composer Software**

HARVEY Composer is a Windows computer program that allows you to conveniently program HARVEY devices as an integrator of PA systems and conferencing systems.

The team behind the HARVEY Composer has set itself the goal of creating an intuitive and time-saving programming environment:

- ➔ HARVEY Composer is the central programming environment for all HARVEY device models: The specific device properties resulting from their features are managed by the HARVEY Composer.
- → Signal processing and control functions are organized as graphically displayed blocks in an audio and control plane.
- ➔ Function blocks are taken from a library area using the drag-and-drop principle and freely placed and connected on a worksheet.
- ➔ Equivalent connections between function blocks are grouped for a better overview. Nevertheless, details in the representation of individual connections are not lost.
- → It is possible to work without a device connection (offline) a resource display also always shows offline the current processor load for the preselected device model.
- → When the HARVEY Composer is connected to a HARVEY device (online), all parameter changes (volume, filter settings, etc.) are performed in real time.
- → Device access can be protected against unauthorized access with a password.
- ➔ The connection to the HARVEY devices takes place via Ethernet network, without requiring special IT skills: All HARVEY devices in the network can be connected to through configurable names.

### **1.2 Information about the HARVEY Devices**

The HARVEY product family is constantly expanding and currently consists of the following members:

- → HARVEY Pro: DSP audio and control matrix flexible equipment with a selectable analogue audio input and output channel count with up to a sum of 32 channels, without / with Dante capability (additional 64 input and 64 output channels) and without / with digital AES capability (additional 2 input and 2 output channels) in one rack unit height.
- ➔ HARVEY mx.16 [Dante] [Cobranet]: Legacy DSP audio and control matrix fixed 16x16 analog input / output channels with / without Dante or Cobranet capability in two height units.
- ➔ HARVEY RC4: Power over Ethernet (PoE) powered control module with four buttons, one rotary knob and RGB signaling for wall, furniture or rack mounting.
- ➔ HARVEY RC12: Power over Ethernet (PoE) powered control module with twelve buttons and RGB signalling for wall, furniture or rack mounting.



See section 6 of this manual for a list of the most typical HARVEY Pro models available.



#### 1.2.1 Flexible programming

All HARVEY devices have a comprehensive set of features that can handle most applications in audio and conferencing systems.

At the same time, there are no rigid processing structures:

- ➔ As a user, you specify the sequence in which the audio signals are to be processed and combined.
- ➔ The control functions range from freely definable state changes through buttons or switches connected to the HARVEY devices, via the possibility of converting interface formats (e.g. from Ethernet to RS232) to a freely configurable web interface for a time-saving creation of end-user terminals.

#### 1.2.2 Powerful Audio signal processing

Thanks to their powerful 32/40 bit signal processors, the HARVEY audio and control matrices have enough processing power to process a large number of channels in real time:

- ➔ For example, a device processes more than 110 channels of 8-band equalizers or 240 seconds of single-block delays or 512 seconds of node delays of a mixing matrix with integrated nodal gain and delay.
- ➔ Depending on the device type, processing and signal conversion takes place with a very small signal delay of 0.75 milliseconds (analog input to output with HARVEY Pro). This delay, also called signal latency, is independent of the number of signal processing or control functions used.

The following processing blocks add delay to an audio signal depending on its block parameters:

- Filters (phase distortion of recursive filters)
- Dynamic blocks (look-ahead time)
- Delay and mixing matrix with delay (delay value)
- → Signal processing works in floating-point format, so you do not have to worry about the quality of a signal going through multiple gain steps - lowering it by 60 dB, for example, and then catching up through amplification will not lead to quality degradation.

## 2 Unpacking


- 1. Please check the carton box for any kind of damage on reception. In case of a damaged carton, please contact your dealer before opening the carton.
- 2. Place the carton on the floor and remove the device.
- 3. Remove all accessories from the carton. You will find the accessories in the lateral compartment.
- 4. For the final use you mount the device in a conventional 19" rack.
- 5. Protect the device from heat, moisture and excessive dust. Consider the maximum ambient operating temperature of the device.
- 6. Connect the device as described in the following sections.

#### Included in delivery carton

- 1 HARVEY<sup>®</sup> device
- 1 3-core power cord (depending on country)
- N 12-positions terminal block; quantity depends on your HARVEY model
- 2 3-positions PHOENIX terminal block
- 1 RS485-/DMX end of line termination resistor 120 Ohm



## 3 Switching on the Device



- 1. Make sure that the device is switched off (press "0") at the rear switch next to the power supply connection.
- 2. Connect the supplied power cord to the device's power supply connection and your mains supply socket.
- 3. Switch on (press "1") at the rear switch next to the power supply connection.
  - > The device starts to boot.
  - > The status light on the front side is yellow during boot.
  - The display on the front side is switched on and informs about the current boot status.
  - As soon as the normal operating status is reached, the main menu is displayed and the status light turns green.
- 4. Establish a network connection between your computer, on which the program HARVEY Composer is installed, and the device. Then start HARVEY Composer to program the HARVEY device. Consult the HARVEY Composer manual for further instructions.

Download the HARVEY Composer software from <u>http://harvey.audio</u> to your computer and install it. You will find the HARVEY Composer User Manual within HARVEY Composer:






See section 4 of this manual for further explanation of the front display, the status light and the menu settings.



See section 5 of this manual for information regarding the interfaces on the rear panel of the device and their technical specification.

## 4 Status and Settings on the Front Panel

On the front of the device, you can make device settings and check the status of the device.



- > The normal operating mode is indicated by a green status light (see section 4.1)
- > Turn the rotary knob left and right to navigate through the menus (see section 4.2ff.).
- > Push the rotary knob to select a menu entry.
- To leave menu entries, navigate to the cross on the right side of the menu's title and push the rotary knob. The main menu will be displayed again.

### 4.1 Status Light

Following table informs about the meanings of the status light on the front side of the device.


Color of Status Light	Status of Device
Green 🔍	Normal operating mode, power supplies ok
Yellow –	Device is booting, power supplies ok
Red 🛡	Problem with power supply; contact your sales partner for further assistance.
Off 〇	Device switched off, no mains power supply or a serious power supply problem; in the latter case contact your sales partner for further assistance.

Under normal conditions the power up sequence is as follows:

Off  $\bigcirc \rightarrow$  Yellow  $\bigcirc \rightarrow$  Green  $\bigcirc$ 

## 4.2 Main Menu

The "Main Menu" is the default display and the starting point for information about the current device status.



There are further display states which are described in section 4.2.5.

#### 4.2.1 Device Status

Consult the "Device Status" menu entry when you want to get informed about the product model and software revisions installed on the device.



With the menu entry "Device Status" highlighted push the rotary knob to enter the entry.

The "Device Status" entry contains following information:

- PR Product model; example "HARVEY 4x0-DA"
- SW Revision text of software update packet which you are able to update via HARVEY Composer; example "2.1.6.0 r7579M"
- SP Revision text of the signal processor's software; this software is included in the software update packet (see "SW"); the revision changes in dependency of the update packet; example "Rev: 7440"
- MS Base system's software revision; this software is included during the factory manufacturing process; example "2.4.0.0 r6837"
- BL Bootloader software revision; this software is included during the factory manufacturing process; example "6544p1"



The "Device Status" is displayed in HARVEY Composer, too, after you connect to the device in question and navigate to the "Service Functions" of the Composer Cockpit.

#### 4.2.2 Network Settings

The entry "Network Settings" enables you to change the network settings of the device's network control interface (see section 5.2 for further information on that interface).

i₄≣A
Network Settings 🛛
HN: HARVEY 4x0 Dante
AM: Dynamic Address
IP: 10.0.10.208
NM: 255.255.255.0
GW: 10.0.10.254
·
Network Settin <del>s</del> s ×
IP: 10.0.10.208
NM: 255.255.255.0
GW: 10.0.10.254
LNK: Link detected
MAC: 3cf52c00048c

With the menu entry "Network Settings" highlighted push the rotary knob to enter the entry.

The "Network" entry contains following information. Some of those settings can be changed by pressing the rotary knob after you navigated to the entry by turning the knob. The location of the cursor is represented by an arrow in front of the entry. The position of the entry in the sub-menu is shown by a scroll bar on the right side.

- HN HARVEY device name: Select the entry by positioning the arrow in front of the entry and press the rotary knob. See section 4.2.2.1.
- AM Address Mode: Changeable between "Dynamic Address" and "Manual Address". See section 4.2.2.2.
- IP IP address: Lets you change the address mode to "Manual Address" and set a new IP address. See section 4.2.2.3.
- NM Network IP mask: Lets you change the address mode to "Manual Address" and set a new network IP mask.
- GW Network IP gateway: Lets you change the address mode to "Manual Address" and set a new network IP gateway.
- LNK This is a status display only. It shows "Link detected" if the HARVEY device has detected a physical Ethernet link, e.g. connected to an Ethernet switch. It shows "No Link!" if there is no physical Ethernet link – check cables and correct functioning Ethernet switch in this case.
- MAC This is a status display only. It informs about the MAC address of the HARVEY device which is additionally labelled on the rear panel of the device below its serial number.

#### 4.2.2.1 Device Name



By entering the HARVEY device name entry...

...you will see the full name of the HARVEY device. The Device Name can be changed within the HARVEY Composer Device Settings in the Cockpit. Pressing the rotary knob leaves this entry.



The "Device Name" can be set within HARVEY Composer, after you connect to the device in question and navigate to the "Device Settings" of the Composer Cockpit.

#### 4.2.2.2 Address Mode

The "Addressing Mode" may be changed between dynamic IP and static IP.

255.255.255.0.

Network Settings ×				
HN: HARVEY 4x0 Dante				
•AM: Dynamic Address				
IP: 10.0.10.208				
NM: 255.255.255.0				
GW: 10.0.10.254				
Network Settings				
Configure manual IP				
address?				
YES CANCEL				
Enter IP Address				
<b>192 168 003 201</b>				
OK Cancel				

By entering the Address Mode entry, which is set to "Dynamic Address" in our example, ...

...you are asked if you want to change it to a static IP address (i.e. manual IP). Pressing the rotary knob on "YES" leads you thru the manual IP settings. Pressing the rotary knob on "CANCEL" leaves the configuration entry unchanged.

You enter an IP address by navigating to the corresponding IP octet. After pressing the rotary knob the field is highlighted and is changed by turning the rotary knob. By pressing again the rotary knob the value is entered and you may proceed to change the next IP octet. Pressing the rotary knob on "YES" confirms the IP address and you get the next screen where the netmask can be set.

Press "CANCEL" to quit the whole manual IP address setting unchanged which leaves the setting to a "Dynamic Address".

Enter IP Netmask
+255 255 255 000
OK Cancel
Enter IP Gateway
Enter IP Gateway +000 000 000 000

Network Settings ×							
HN: HARVEY 4x0 Dante	1						
•AM: Manual Address							
IP: 10.0.10.99							
NM: 255.255.255.0							
GW:							
Network Settings							
Switch to dynamic IP							
addressin9?							
YES CANCEL							

Enter the IP gateway. Normally this can be left unchanged to 0.0.0.0. Needs only be set if device is to communicate with devices in other networks than the local network.

Enter the IP netmask. In normal cases this can be left unchanged to

By entering the Addressing Mode entry, which is set to "Manual Address" in our example, ...

...you are asked if you want to change it to a dynamic IP address. Pressing the rotary knob on "YES" confirms this setting. Pressing the rotary knob on "CANCEL" leaves the configuration entry unchanged.

The dynamic IP addressing lets the device first to browse for a DHCP server on the network. Consult the settings of that DHCP server to administer the IP settings for the DHCP network clients.



If there is no DHCP server on the network the HARVEY device will start its so called Auto IP procedure. As a result it will set itself IP settings with a free IP address out of the standardized Auto IP address range 169.254.0.1 through 169.254.255.254 with a subnet mask 255.255.0.0. The HARVEY device requires a network link to be able to check and set such an IP address.



The Address Mode may be changed with the help of HARVEY Composer Cockpit under the Device Settings, too.



#### 4.2.2.3 IP Address

Network Settin <del>s</del> s ×				
HN: HARVEY 4x0 Dante				
AM: Dynamic Address				
NM: 255.255.255.0				
GW: 10.0.10.254				
Network Settings				
Network Settings Configure manual IP				
address?				
YES CANCEL				
VES CANCEL				
Enter IP Address				
Enter IP Address				
Enter IP Address				

By entering the "IP Address" entry, when the device is set to "Dynamic	
Address" in our example,	

...you are asked first if you want to change it to a static IP address (i.e. manual IP). Pressing the rotary knob on "YES" leads you thru the manual IP settings. Pressing the rotary knob on "CANCEL" leaves the configuration entry unchanged.

You enter an IP address by navigating to the corresponding IP octet. After pressing the rotary knob the field is highlighted and is changed by turning the rotary knob. By pressing again the rotary knob the value is entered and you may proceed to change the next IP octet. Pressing the rotary knob on "YES" confirms the IP address and you get the next screen where the netmask can be set. Press "CANCEL" to quit the whole manual IP address setting

unchanged which leaves the setting to a "Dynamic Address". Enter the IP netmask. In normal cases this can be left unchanged to 255.255.0.

Enter IP Netmask
+255 255 255 000
OK Cancel
Enter IP Gateway
•000 000 000 000
OK Cancel

Network Settings ×
HN: HARVEY 4×0 Dante
AM: Manual Address
IP: 10.0.10.99 NM: 255.255.255.0
NM: 200.200.200.0
Enter IP Address
▶192 168 003 201
OK Cancel

Enter the IP gateway. In normal cases this can be left unchanged to 0.0.0.0.

By entering the "IP Address" entry, when the device is set to "Manual Address" in our example, ...


You are directly asked to enter an IP address by navigating to the corresponding IP octet. After pressing the rotary knob the field is highlighted and is changed by turning the rotary knob. By pressing again the rotary knob the value is entered and you may proceed to change the next IP octet.

Pressing the rotary knob on "YES" confirms the IP address and you get back to the main menu.

Press "CANCEL" to quit the manual IP address setting unchanged and gets you back to the main screen.

#### 4.2.3 Device Connections

The entry "Device Connections" is a status display in the context of Hypermatrix projects. See the HARVEY Composer Operating Manual for further information in Hypermatrix.



With the menu entry "Device Connections" highlighted push the rotary knob to enter the entry.

The example display aside shows a Hypermatrix group of four devices: The check marks in front of the three devices in the list show that the current device (the one you are looking at) is able to communicate with the other three Hypermatrix devices.

The example display aside shows a Hypermatrix group of four devices: The exclamation mark in front of the first device shows that the current device (the one you are looking at) is NOT able to communicate with that device.

In this case you have to check for a correct network cabling and power supply of that device.

#### 4.2.4 Alarms

The "Alarms" sub-menu lists all current errors of the device.



With the menu entry "Alarms" highlighted push the rotary knob to enter the entry.

Normally there should be no alarms displayed in the list.

#### 4.2.5 Other Display States

#### 4.2.5.1 Boot Screens

After switching on the device shows the boot process until it shows the main menu.

#### 4.2.5.2 Sound Off



Whenever the crossed speaker symbol appears in the right corner of the main menu, the device's sound is globally switched off. If there is no speaker symbol displayed, the sound is globally switched on.



You can change the sound setting in HARVEY Composer. Either in the worksheet's status bar or in the Cockpit's Device Settings when connected to the device.

Be aware, that HARVEY Composer automatically switches off the sound, each time you upload a project to the device. Do not forget to switch it on manually.

#### 4.2.5.3 Screensaver

After 1 minute without user input the display enables its screensaver and the display is switched off.


> By turning or pushing the rotary knob you are able to re-enable the display.

#### 4.2.5.4 Project Loading

When transferring a project to the device with the help of HARVEY Composer the name of the project name is temporarily shown on the display.

## 5 Interfaces on the Rear Panel

## 5.1 Mains Power Supply Inlet



Interface	Mains power supply inlet
Connector	3-positions appliance power inlet C14 IEC60320-1 with integrated mains switch
Ratings	100-240V a.c. 50-60 Hz, rated current draw depends on device model and is indicated on type plate
Safety	No exchangeable fuse



### ATTENTION

The device must be operated via the included three-core mains power cord connected to a socket-outlet with earthing connection.



#### ATTENTION

Before use, always make sure that the power cord is in good condition. Dispose and replace a damaged power cord immediately. Never detach the protective earthing conductor of the power cord.




#### ATTENTION

Be sure to connect the device to a mains installation only, which is equipped with an overcurrent protective device.

## 5.2 Network Control Interface

One network control interface is part of the standard HARVEY Pro equipment. It is used for different purposes:

- Connection and programming the device with the PC software HARVEY Composer
- HARVEY device interaction in a multi-HARVEY system (Hypermatrix)
- Media control integration




10/100 Mbps Ethernet, compliant with IEEE802.3/802.3u (100BaseT) Interface and ISO802-3/IEEE802.3 (10BaseT), auto-negotiation, automatic polarity detection and correction, auto-MDIX support									
Connector 8 position 8 contact (8P8C) modular connector socket, shielded RJ45									
	1	2	3	4	5	6	7	8	
Pinout	TD+	TD-	RD+	-nc-	-nc-	RD-	-nc-	-nc-	
Connector shield connects to device enclosure.									
				Off		On		Flashing	
LED Indicators	Right green LED			no physical link		physical link w/o data activity		physical link with data activity	
	Left yellow LED			10 Mbps		100 Mbps		-not applicable-	
Recommended Cable	Minimur pinout.	m CAT5	i twiste	d pair ca	ble witl	h RJ45 co	onnecto	r accord	ling to



### 5.3 RS232 Control Interface

One RS232 interface is part of the standard HARVEY Pro equipment. It is used for:

Media control integration



Interface	RS232, Data Communication Equipment (DCE)								
Connector		D-SUB9/DE-9 socket with a pair of #4-4unc nuts for fixing a mating male connector							
	1	2	3	4	5	6	7	8	9
	-nc-	TxD	RxD	DTR	GND	DSR	CTS	RTS	-nc-
Pinout	-na-	output	input	input	-na-	output	input	output	-na-
	Pins #4 (DTR) and #6 (DSR) are connected internally. Connector shield connects to device enclosure.								
Protocol Capabilities	Baud rates: 9600, 19200, 38400, 57600, 115200, 230400, 460800 Data bits: 7, 8 Stop bits: 1, 2 Parity: none, odd, even Flow control: none, XON/XOFF, RTS/CTS								

## 5.4 RS485 / DMX Control Interface


One RS485 / DMX interface is part of the standard HARVEY Pro equipment. It has a dual use function which is configured in HARVEY Composer: RS485 or DMX512-A.

As a RS485 interface it is used for:

Media control integration

As a DMX interface it is used as a:

- DMX universe controller, i.e. DMX512 output
- or
- DMX device, i.e. DMX512 input



Interface	One RS485 half-duplex endpoint, differential mode of operation, galvanically isolated, two connectors for easy integration into cabling topology (bus, star, etc.)						
Connector	Two 3-pole	PHOENI	( male term	ninal 3.81 mm pitch			
Connector	Mating con	nector (inc	luded in de	elivery): PHOENIX part#1803581			
	1	2	3				
Pinout	DATA-	Shield GND	DATA+				
T mout	DATA+/- and Shield GND are galvanically isolated (up to 1 kV <sub>rms</sub> ) internal potentials.						
RS485 Protocol Capabilities	Baud rates Data bits: 7 Stop bits: 1 Parity: non	Half-duplex bi-directional Baud rates: 9600, 19200, 38400, 57600, 115200, 230400, 460800 Data bits: 7, 8 Stop bits: 1, 2 Parity: none, odd, even Flow control: none, XON/XOFF, RTS/CTS					
DMX Protocol	Compliant with DMX512 either sender or receiver configured by HARVEY Composer						
Recommended Cable	100120 Ohm impedance shielded twisted pair						





Connect the cable shield only to one end of the cable to avoid ground loops.



#### Terminate the data lines:


In a straight line topology terminate with a 120 Ohm resistor at each end of the line – i.e. at the first and last RS485/DMX device of a line. In a star topology terminate at the star point device and at each end of the star.



## 5.5 Digital Input Control Interface (GPI)

Four digital control inputs are part of the standard HARVEY Pro equipment. These general purpose control inputs (GPI) are used for


- Preset calls
- Muting individual channels or channel groups
- Triggering serial command transmissions
- Other logic functions



Interface	Four independent general purpose inputs (GPI) for logic control					
Connector	8 pins of a 12-pole PHOENIX male terminal 3.81 mm pitch					
Connector	Mating connector (included in delivery): PHOENIX part#1803675					
Pinout	see figure above					
Capabilities	User may connect a tactile switch (dry contact), a voltage source or a variable resistor between GPI and GND					
	see wiring diagrams on following page					
Switch current (Option A)	$I_{switch} = 300 \ \mu A @ R_{ext} = 0 \ \Omega$					
Switching thresholds	$R_{ext,th} = 10 \ k\Omega \ (\pm 10\%)$					
(Options B, C)	$U_{ext,th}$ = +1.6 V (±10%) – measured at GPI with reference to GND					
Maximum operating limits (Option C)	$U_{ext} = -5 V \dots +5 V$ (steady state, GPI with reference to GND)					



#### **GPI** Wiring Options






## 5.6 Analog Input Control Interface (AIN)

Two analog control inputs (AIN) are part of the standard HARVEY Pro equipment. These analog inputs are used for:


Continuous control of gain faders



Interface	Two independent analog inputs (AIN) for continuous fader control, reference voltage output (+V) and reference ground (GND) present, internally calibrated with reference to actual +V											
Connector	•	4 pins of a 12-pole PHOENIX male terminal 3.81 mm pitch										
	Mating conne		(Inclue	ded ir	n deliv	/ery):	РНО	ENIX	part#	1803	675	
Pinout	see figure ab	ove										
Capabilities	User may co	nnect	a pot	entio	meter	or a	volta	ge so	urce			
Capabilities	see wiring dia	agran	ns on	follov	ving p	age						
Recommended potentiometer (Option A)	Linear type Nominal resistance $R_{nom} = 1 \ k\Omega \dots 100 \ k\Omega$											
Relative resistance-to-	Relative to R <sub>nom</sub> [%] *)	0	10	20	30	40	50	60	70	80	90	100
gain correlation	Gain [dB]	-∞	-89	-78	-67	-56	-45	-34	-23	-12	-1	+10
(Option A)	(Option A) *) Relative to R <sub>nom</sub> [%] is the resistance value seen by the input between terminals / and GND in relation to the resistance seen between terminals +V and GND.					s AIN						
Absolute	UAIN [V]	0	0.47	0.94	1.41	1.88	2.35	2.82	3.29	3.76	4.23	4.7
voltage-to-gain	Gain [dB]	-∞	-89	-78	-67	-56	-45	-34	-23	-12	-1	+10
correlation (Option B)	Table valid for unloaded +V.											
Maximum operating limits (Option B)	$U_{AIN} = -0.5 V \dots +5 V$ (steady state, AIN with reference to GND)											




#### **AIN Wiring Options**



## 5.7 Digital Output Control Interface (GPO)

Four digital control outputs are part of the standard HARVEY Pro equipment. These general purpose control outputs (GPO) are used for


- Directly driving external LED indicators
- Switching externally supplied loads (e.g. relays)



Interface	Four independent general purpose outputs (GPO) for directly driving external LED indicators or externally supplied loads (e.g. relays)
Connector	8 pins of a 12-pole PHOENIX male terminal 3.81 mm pitch
	Mating connector (included in delivery): PHOENIX part#1803675
Pinout	see figure above
Capabilities	see wiring diagrams on following page
Direct drive	$I_{d}$ = (4.8 V – $U_{f})$ / 100 $\Omega$ ; $U_{f}$ := LED forward voltage
Direct drive current capability	$I_{d,max} = 48 \text{ mA} @ Uf = 0 \text{ V}$
(Option A)	In case you need a lower LED current, externally integrate an appropriate resistor in series with the LED.
Operating limits for external supply	$U = +5 \text{ VDC} \dots + 30 \text{ VDC}$ Choose a power supply in accordance to the voltage range.
(Option B)	I <sub>max</sub> = 75 mA Choose a relay (or other load) in accordance to this limit.



#### **GPO Wiring Options**






## 5.8 Relay Contact Interface (GPO)

Two relay contact pairs are part of the standard HARVEY Pro equipment. These dry general purpose control outputs (GPO) are used for

- Switching externally supplied loads (e.g. relays)
- Galvanically isolated switching of other system components' GPIs




Interface	Two independent switch contact pairs (GPO)
Connector	4 pins of a 12-pole PHOENIX male terminal 3.81 mm pitch
Connector	Mating connector (included in delivery): PHOENIX part#1803675
Pinout	see figure above
	Both switches are "normally open" (NO)
Capabilities	<ul> <li>"1/TRUE" : switch closed</li> </ul>
	<ul> <li>"0/FALSE" : switch open</li> </ul>
Rated load	DC: 1.0 A @ 30 VDC; 0.5 @ 60 VDC (60 VDC max.); 30 Wmax.
(resistive load)	AC: 1.0 A @ 30 VAC; 0.3 A @ 125 VAC (125 VAC max.); 37 VAmax.

## 5.9 Dante Network Audio Interface (Optional)

The Dante network audio interface is an optional HARVEY Pro component.

It is provided including following features:

- Endpoint for 64x64 audio channels; each 48 kHz/24 bit
- Primary and secondary interface available supporting Dante redundancy mode and switch mode



Interface	module IEEE80	Audinate Dante® network audio, realised based on Audinate´s BK-II module (64x64), two ports 100/1000 Mbps Ethernet, compliant with IEEE802.3/802.3u (1000BaseT/100BaseTX), auto-negotiation, automatic polarity detection and correction, auto-MDIX support									
Connector	Two 8 p RJ45	Two 8 position 8 contact (8P8C) modular connector sockets, shielded RJ45									
	1	2	3		4	5		6	7	8	
Pinout	D1+	D1-	D2+	F	D3+	D3-		D2-	D4+	D4-	
	Connec	Connector shield connects to device enclosure.									
		Off On Flashing									
LED Indicators	Right	Right green LED         no physical link         physical link w/o data activity         physical link with data activity									
	Left yellow LED         100 Mbps         1000 Mbps         -not applicable-										
Recommended Cable	Minimur pinout.	m CAT5	twist	ed	pair cat	ole wit	th F	RJ45 cc	onnecto	r accord	ing to




## 5.10 Analog Audio Line Output Interface

The quantity and physical position of the analog audio line output interface depends on the actual HARVEY Pro model. HARVEY Pro devices may be equipped with multiples of eight line outputs up to 32 channels.

HARVEY Harver V Harver V						
	Channel number 1 2 3 4					
	$ + - \not \neg \neg   + - \not \neg \neg   + - \not \neg \neg  $					
Cha	annel numbers are counted from 5 6 7 8					
	As an example an eight line-out HARVEY device is shown.					
	+ - /// + - /					
	Analog audio line outputs, number of channels 8/16/24/32 dependent on device model, balanced floating line level output, AC coupled, protected					
Interface	against overcurrent and overvoltage,					
	based on THAT Corp. OutSmarts® balanced line driver					
Connector for	2x 12-pole PHOENIX male terminal 3.81 mm pitch					
eight channels	Mating connector (included in delivery): PHOENIX part#1803675					
	+/- balanced line outputs					
Pinout	shield, connected to chassis internally (AES-48)					
Wining						
Wiring	see wiring diagrams on following page					
Gain settings	+15 dB, +9 dB, +6 dB, 0 dB					
	+24 dBu, +18 dBu, +15 dBu, +9 dBu (unloaded, THD+N 1%)					
Output levels	+22 dBu, +16 dBu, +13 dBu, +7 dBu (600 Ω load, THD+N < -100 dB)					
	(rated minimum load: 600 Ω)					
Output impedance	70 Ω balanced					
Bandwidth	35 Ω unbalanced					
	10 Hz 22.5 kHz (-0.3 dB / -1.0 dB rel. 1 kHz)					
Channel Crosstalk	< -104 dB @ +24 dBu level (worst case)					
Dynamic range	> 110 dB @ 600 Ω load, all gain settings					
THD+N	< -103 dB @ 16 dBu / 997 Hz, 600 $\Omega$ load, +9 dB gain setting					
D-to-A converter	48 kHz / 24 bit, delta-sigma					
D-to-A latency	125 µs					



**Recommended Line Output Wiring** 





Whenever possible avoid a connection to unbalanced signal level equipment because audio performance will be sacrificed.



### 5.11 Analog Audio Mic / Line Input Interface

The quantity and physical position of the analog audio line output interface depends on the actual HARVEY Pro model. HARVEY Pro devices may be equipped with multiples of four mic / line inputs up to 28 channels.

	Channel number $1 2 3 4$ $1 - m + -m + -m + -m$
	Channel numbers are counted from left top to right bottom. As an example an eight mic / line input HARVEY device is shown.  + - dt  + - dt  + - dt  + - dt
Interface	Combined analog audio microphone and line inputs, number of channels 4/8/12/16/20/24/28 dependent on device model, balanced floating line level input, P48 phantom voltage switchable, AC coupled, protected against overcurrent and overvoltage, based on THAT Corp. differential preamplifier
Connector for four channels	1x 12-pole PHOENIX male terminal 3.81 mm pitch Mating connector (included in delivery): PHOENIX part#1803675
Pinout	<ul> <li>+ / - balanced line inputs</li> <li>h shield, connected to chassis internally (acc. AES-48)</li> </ul>
Wiring	see wiring diagrams on second after next page
Preamp gain	Mic: 0…+60 dB, 3 dB steps Line: 0, +6, +9, +15 dB
Line Input levels	+24 dBu, +18 dBu, +15 dBu, +9 dBu (THD+N 1%)
Line input levels	+22 dBu, +16 dBu, +13 dBu, +7 dBu (THD+N < -100 dB)
Input	2 kΩ balanced
impedance	1 kΩ unbalanced
Phantom power (P48)	+48 VDC, 10 mA max. (IEC 61938), switchable for each input
	NTION re to exclusively enable phantom power for condenser microphones

Be sure to exclusively enable phantom power for condenser microphones which are specified for a P48 supply. Other equipment could be harmed!

Table continues on following page...




...continuation of the previous page:

Mic EIN	-127.5 dBu @ 22 kHz bandwidth with 150 $\Omega$ source impedance
Bandwidth	10 Hz … 22.5 kHz (-0.3 dB / -1.0 dB rel. 1 kHz)
Channel Crosstalk	< -104 dB @ +24 dBu level (worst case)
Dynamic range	> 110 dB, all gain settings
THD+N	< -101 dB @ 997 Hz, 0 dB gain setting
A-to-D converter	48 kHz / 24 bit, delta-sigma
A-to-D latency	333 µs



**Recommended Line Input Wiring** 



## 6 HARVEY Pro Models

The most typical device models of HARVEY Pro are listed in the following table:

1 HU, 19" DSP audio matrix with
8 analog audio inputs, 8 analog audio outputs
8 analog audio inputs, 8 analog audio outputs, 64 Dante digital audio inputs, 64 Dante digital audio outputs
<ul> <li>8 analog audio inputs, 8 analog audio outputs,</li> <li>64 Dante digital audio inputs, 64 Dante digital audio outputs,</li> <li>1 AES digital audio input, 1 AES digital audio output (i.e. 2x2 channels)</li> </ul>
12 analog audio inputs, 8 analog audio outputs
12 analog audio inputs, 8 analog audio outputs, 64 Dante digital audio inputs, 64 Dante digital audio outputs
16 analog audio inputs, 8 analog audio outputs
16 analog audio inputs, 8 analog audio outputs, 64 Dante digital audio inputs, 64 Dante digital audio outputs
8 analog audio inputs, 16 analog audio outputs
8 analog audio inputs, 16 analog audio outputs, 64 Dante digital audio inputs, 64 Dante digital audio outputs
16 analog audio inputs, 16 analog audio outputs
8 analog audio inputs, 24 analog audio outputs
24 analog audio inputs, 8 analog audio outputs
8 analog audio outputs, 64 Dante digital audio inputs, 64 Dante digital audio outputs
4 analog audio inputs, 64 Dante digital audio inputs, 64 Dante digital audio outputs
8 analog audio inputs, 8 analog audio outputs, 64 Dante digital audio inputs, 64 Dante digital audio outputs 4 class-D amplifier outputs (max. 80 W per unit) <i>This model is only available with CE marking.</i>

Please contact us, if you require other interface combinations. The chances are high that we can make further models available.

### 6.1 HARVEY Pro versus HARVEY mx.16

The following table lists the commons and differences between the HARVEY Pro devices and the legacy HARVEY mx.16 unit.

Property	HARVEY Pro NxM[-DA][-AES][-AMPn]	HARVEY mx.16[Dante][Cobranet]
Number of Analog	N analog audio inputs in steps of 4	16 analog inputs
Audio Channels	M analog audio outputs in steps of 8	16 analog outputs
NxM	Up to a sum of 32 channels $(N+M = 32)$	
Dante Option	64 Dante digital inputs	16 Dante digital inputs
[-DA]	64 Dante digital outputs	16 Dante digital outputs
CobraNet Option	Not available	16 CobraNet digital input
		16 CobraNet digital outputs
Mic Inputs (Number und Gain)	Each analog input is mic capable (P48 and gain)	Only the first eight channels are mic capable (P48 and gain)
	Gain range: 060 dB in 3 dB steps	Gain range: 0, 1065 dB in 1 dB steps
Line Inputs (Gain-Steps)	Each analog audio input is line level capable.	Each analog audio input is line level capable.
	Gain steps: 0, 6, 9, 15 dB	Gain steps: 0, 9, 15, 18 dB
Line Outputs (Gain Steps)	Each analog audio output is line level capable.	Each analog audio output is line level capable.
	Gain steps: 0, -6, -9, -15 dB	Gain steps: 0, -9, -15, -18 dB
Switching Inputs (GPI)	Four switching inputs	Eight switching inputs
Switching Outputs	Six switching outputs, of which	Three switching outputs
(GPO)	- Four transistor outputs, each with two connection options: supplied internally, externally powered	- no transistor outputs
	- two relay switches	- three relay switches
Voltage Inputs	Two voltage inputs	Eight voltage inputs
AES3 Option	One AES Rx, One AES Tx	Not available
[-AES]	2 digital AES3 compatible input channels 2 digital AES3 compatible output channels	
Amp Option [-AMPn]	4/8/12 amplifier outputs	Not available

# 7 HARVEY Pro Specifications Summary

Signal Processing	
Sampling Rate	48 kHz
Raw Processing Capacity	450 MIPS / 2.7 GFLOPS
Delay Memory	240 seconds of block delay

Analog Audio Inputs	
Number of Inputs	Dependent on device model: 0, 4, 8, 12, 16, 20, 24, 28
Connectors	3-positions on PHOENIX 3.81 mm pitch per input channel
Basic Specification	Balanced floating line / mic level inputs; AC coupled
Preamp gain	Mic: 0…+60 dB, 3 dB steps Line: 0, +6, +9, +15 dB
Line Input Levels	+24 dBu, +18 dBu, +15 dBu, +9 dBu (THD+N 1%)
	+22 dBu, +16 dBu, +13 dBu, +7 dBu (THD+N < -100 dB)
Phantom power (P48)	Switchable independent for each input; 48 V / 10 mA max. (IEC 61938)
Mic Equivalent Input Noise (EIN)	-127.5 dBu @ 22 kHz bandwidth with 150 Ohm source impedance

Analog Audio Outputs			
Number of Outputs	Dependent on device model: 0, 8, 16, 24, 32		
Connectors	3-positions on PHOENIX 3.81 mm pitch per input channel		
Basic Specification	Balanced floating line level outputs; AC coupled		
Gain Settings	+15 dB, +9 dB, +6 dB, 0 dB		
Line Output Levels	+24 dBu, +18 dBu, +15 dBu, +9 dBu (unloaded, THD+N 1%)		
	+22 dBu, +16 dBu, +13 dBu, +7 dBu (600 Ω load, THD+N < -100 dB)		
	(rated load: $\geq$ 600 $\Omega$ )		

Common Analog Audio Quality Specs			
Bandwidth	10 Hz 22.5 kHz (-0.3 dB / -1.0 dB rel. 1 kHz)		
Dynamic Range	< -110 dB unweighted		
THD+N (A/D/A)	< -100 dB @ 997 Hz, 0 dB gain settings		
Channel Crosstalk	< -104 dB @ +24 dBu		
Latency (A/D/A)	< 0.75 ms (analog audio inputs routed to analog audio outputs)		



Common Interfaces (all models)			
Front User Interface	128x64 pixel OLED graphics display (black/white); rotary knob with integrated pushbutton; 3-color status LED light		
Network Control Interface	RJ45 w/ two LEDs; 10/100 Mbps (100BaseTX/10BaseT), CAT5 or better recommended; media control and programming		
RS232 Control Interface	D-SUB9 socket/female; baud rates 9,600 – 460,800 bps; media control		
RS485 / DMX Control Interface	Two 3-positions PHOENIX male terminals 3.81 mm pitch, baud rates 9,600 – 460,800 bps; galvanically isolated; media control and DMX512 sender/receiver		
Digital Input Control Interface (GPI)	Four inputs on 8 pins of PHOENIX male terminal 3.81 mm pitch; external switch, external resistor/potentiometer (threshold 10 kOhm), external voltage source (threshold 1.6 VDC)		
Analog Input Control Interface (AIN)	Two inputs on 4 pins of PHOENIX male terminal 3.81 mm pitch; external potentiometer (nom. value 1 kOhm 100 kOhm), external voltage source (0+4.7 VDC)		
Digital Output Control Interface (GPO)	Four outputs on 8 pins of PHOENIX male terminal 3.81 mm pitch; capable of directly driving external LEDs (or similar loads, 48 mA max.), indirectly driving externally supplied loads (e.g. relays, external voltage +5+30 VDC, 75 mA max.)		
Relay Contact Interface (GPO)	Two independent switch contact pairs on 4 pins of PHOENIX male terminal 3.81 mm pitch; each 1 A @ 30 VDC (30 W max.); 1.0 A @ 30 VAC (37 VA max.)		

Dante Audio Network Interface (Option "-DA")				
Number of Channels	64 input channels / 64 output channels			
Connectors	Two RJ45 w/ two LEDs; 100/1000 Mbps; Dante primary and secondary interface (switched or redundant)			
Channel Routing	Automatic by HARVEY Hypermatrix or manually with Audinate's Dante Controller			

AES3 Audio Interface (Option "AES")			
Number of Channels	1x AES-RX (2 channels), 1x AES-TX (2 channels);		
Connectors	Two 3-positions PHOENIX 3.81 mm pitch;		
	XLR option on request		
Data Sampling Rate	Input 8 kHz 192 kHz (sampling rate converted to 48 kHz)		
	Output 48 kHz (fixed)		
Termination	110 Ohm; transformer isolated		



Class-D Ampliner Output (Option AMP4 )					
Number of Channels	4x amplifier outputs; more channels possible on request (up to 12)				
Connectors	Four 3-positions PHOENIX 5,0 mm pitch				
Speaker impedance	≥ 2 Ohm				
Output Power	Dut PowerMax. 80 Watt in total per unit; automatic power limit independent of loadFor equally driven channels power per channel:Load1 ch.2 ch.3 ch.4 ch.				
					4 ch.
	2 Ohm	1x 82 W	2x 41 W	3x 27 W	4x 20 W
	4 Ohm	1x 63 W	2x 41 W	2x 27 W	4x 20 W
	8 Ohm	1x 32 W	2x 32 W	2x 27 W	4x 20 W
THD+N	< 0.1%				

General (all models)				
Mains power supply	3-positions C14 IEC60320-1 with integrated mains switch; 100-240 V ~ 50 / 60 Hz, see table on following page for power values			
Ambient temperature	0 °C - 30 °C / 32 °F - 86 °F Ensure that left and right device sides are unobstructed (25 mm minimum clearance on both sides).			
Cooling	Models with less than a sum of 24 analog audio input and output interfaces: Convection All other models: Fan, left to right			
Humidity	10% to 90%, noncondensing			
Shipping weight (examples)	HARVEY Pro 16x16: 3.1 kg; HARVEY Pro 4x0-DA: 2.9 kg			
Dimensions	1 RU height; for integration in standard 19" rack; WDH: 482 mm x 193 mm x 43.8 mm (dimensions include 19" mountir brackets)			
Regulatory compliance, certifications	Safety: CE, IEC/UL 62368-1:2014 (CB and NRTL listed mark)			
	EMC: CE, EN 55032:2012 Class A, EN 55035:2017, EN 61000-3- 2:2014, EN 61000-3-3:2013, FCC 47 CFR Part 15 Class A, ICES-3(A)			
	RoHS: CE, EN 50581			

#### Class-D Amplifier Output (Option "AMP4")

Electrical power, thermal output (per model)				
Pro	True power input requirement <sup>1)</sup>	BTU/h <sup>2)</sup>		
8x8	22 W	66 BTU/h		
8x8-DA	24 W	75 BTU/h		
8x8-DA-AES	26 W	82 BTU/h		
12x8	27 W	81 BTU/h		
12x8-DA	29 W	90 BTU/h		
16x8	36 W	114 BTU/h		
16x8-DA	39 W	121 BTU/h		
8x16	35 W	106 BTU/h		
8x16-DA	37 W	115 BTU/h		
16x16	44 W	135 BTU/h		
8x24	43 W	129 BTU/h		
24x8	46 W	142 BTU/h		
0x8-DA	15 W	46 BTU/h		
4x0-DA	12 W	38 BTU/h		
8x8-DA-AMP4	tbd	tbd		

<sup>1)</sup> True power drawn by model under rated conditions,
 i.e. 0 dBFS into 600 Ohm loads on all analog audio outputs,
 P48 10 mA current supply of all analog audio inputs

 $^{2)}$  True power drawn by model, external power of loads excluded, 1 W = 3.41 BTU/h



#### CONTACT

DSPECIALISTS Digitale Audio- und Messsysteme GmbH

Helmholtzstr. 2-9L

10587 Berlin

Germany

Phone +49 30 467 805-0 Fax +49 30 567 805-99

sales@dspecialists.de www.dspecialists.de



www.harvey.audio

